

GUJARAT BIOTECHNOLOGY UNIVERSITY

GIFT City, GIFT City Road, Shahpur Village, Gandhinagar- 382355

Email: info-gbu.gujarat.gov.in
Website: www.gbu.edu.in/



Corrigendum IV

Request for Proposal (RFP) for appointment of Contractor for Residential Facilities at Gujarat
Biotechnology University, Gandhinagar

E-Tender No.: 01 of 2023-24, Tender ID: 9814

Corrigendum IV

S. No	Clause	Original Clause	Modified Clause / New Clause		
1.	Data Sheet	Last date and time of Submission of bids (Offline): 24/11/2023	Last date and time of Submission of bids (Offline): 08/12/2023 Up		
	S.N. 11 and	Up to 18:00 hours IST	to 17:00 hours IST		
	Clause 1.3				
2.	Data sheet	Date and Time for Opening of Technical Bids	09/12/2023 at 12:00 pm hours IST		
	S.N. 12 and	· -			
	Clause 1.4				

Note:

1. The clarifications/ changes given are applicable for all similar section/clause in the entire RFP document.

Construction of Residential Facilities at Gujarat Biotechnology University									
S. No	Item No	SOR No	Description	Unit	Previous Quantity	Revised Quantity			
1	16	5057	Providing and laying in position Ready Mixed M-300 grade concrete for reinforced cement concrete work, using cement content as per approved Design Mix manufactured in fully automatic batching plant and transported to site of work in transit mixer to a lead up to 10kms having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS:9103 to accelerate / retard setting of concrete ,improve workability without impairing strength and durability as per direction of the Engineer- in-charge. Without Fly Ash	Cum	13812	14364			
2	20	09001CA	Providing form work of ordinary timber planking so as to give a rough finish including centering shuttering strutting and propping etc. Height of propping and centering below supporting floor to ceiling not exceeding 4M. and removal of the same for in-situ reinforced concrete and plain concrete working. (C) Vertical surface such as walls (any thickness) partitions and the like including attached buttresses & string course & the like.	Sqm	6040	6040			